



- Notes
- 1) Island Nose constructed from Limestone Blocks. Over / most exposed blocks to have a diameter greater than 1.5m and typical mass of 4.5t to 5t. Inter-spaced with smaller blocks to provide support and stability. Blocks dimensions to diminish with increased cover and proximity to bank.
 - 2) Coppicing of trees on the island to be undertaken, pending negative bat surveys.

Part Buried Live Willow Logs
(Stone to be ~30kg or 270mm dia)

Rev	Date	Description	Chd	Ver'd
1	25-10-07	Willow Arrangement Modified	AL	AL
2	23-11-07	Coppicing Added, Grove A1 removed	AL	AL

PROJECT
Symonds Yat In-Fliver Works
Canoe Rapids & Habitat Improvements



TITLE
Island Stabilisation and Habitat Improvements

SCALE	DRAWN	AL	DATE
1:500	CHECKED	JE	September 07
SIZE	VERIFIED	AL	
DATE	DRAWING NO.	REV.	
Planning / RDC	04-1106-130	2	



41 Awinton Tor, Newcastle upon Tyne, NE3 1LD.
Telephone: 07309 441573
Email Address: [first.name]_[surname]@epduk.com
www.epduk.com